SERVICE BULLETIN



Vibratory Hammers • Power UnitsAuger Systems • Diesel & Hydraulic Hammers

Drill Rigs • Hydraulic Piling Rigs • Wick Drain Installers • Lead Systems

Dec. 30, 2014



www.jandm-usa.com

#9 Test Switch On Panel



This bulletin is to address the possible danger of the engine not being able to be shut off because of the **NORMAL/TEST** switch in the panel. If you select the test option while the engine is running there is no way to shut the engine off safely. The switch will have to be put back in the normal position to be able to use the **OFF** and **E-STOP** selections.

One example of this issue is if a technician is using a remote/jumper starting switch while in test mode. Once the engine is cranked over with the remote switch it will start and won't be able to be shut off until put back into normal mode.

The test switch is used only for setting engine parameters with the MFG. SOFTWARE.

APE HEADQUARTERS
7032 S 196th Street
Kent, WA 98032
(800) 248-8498 * (253) 872-0141
Fax (253) 872-8710

Northeast Regional Office 401 Hartle St. Sayrewille, NJ 08872 (888) 217-7524 • (732) 432-6604 Fax (732) 432-6608 APE CHINA
BUILDING NO. 233, FU QIAO ROAD
GU CUN INDUSTRIAL ZONE BAOSHAN DISTRICT
SHANGHAI, CHINA 201906
011-86-21-3604-0553

LOUISIANA REGIONAL OFFICE 39266 A DOVILE DRIVE GONZALES, LA 70737 (225) 644-7722 FAX (225) 644-7626 GULF REGIONAL OFFICE 3975 FM Hwy 1485 CONROE, TX 77306 (800) 596-2877 • (936) 271-1044 FAX (936) 271-1046